# **ENGLISH TRANSLATION**

# 700 MHz BAND INTELLIGENT TRANSPORT SYSTEMS — TEST ITEMS AND CONDITIONS FOR MOBILE STATION INTEROPERABILITY VERIFICATION

## **GUIDELINE**

ITS FORUM RC-011 Ver. 1.0

Established on May 31, 2012

ITS Info-communications Forum of Japan



# General Notes to the English Translation of ITS Info-communications Forum Guidelines

#### 1. Notes on Copyright

- The copyright of this document is ascribed to the ITS Info-communications Forum of Japan.
- All rights reserved. No part of this document may be reproduced, stored in a retrieval system or transmitted, in any form or by any means, without the prior written permission of ITS Info-communications Forum of Japan.

#### 2. Notes on English Translation

- ITS Info-communications Forum Guidelines are usually written in Japanese. This document is a translation into English of the original document for the purpose of convenience of users. If there are any discrepancies in the content, expressions, etc. between the original document and this translated document, the original document shall prevail.
- ITS Info-communications Forum Guidelines, in the original language, are made publicly available through web posting. The original document of this translation may have been further revised and therefore users are encouraged to check the latest version at an appropriate page under the following URL:

http://www.itsforum.gr.jp/Public/Eguideline/index.html.

# 700 MHz BAND INTELLIGENT TRANSPORT SYSTEMS — TEST ITEMS AND CONDITIONS FOR MOBILE STATION INTEROPERABILITY VERIFICATION

# **GUIDELINE**

ITS FORUM RC-011 Ver. 1.0

Established on May 31, 2012

ITS Info-communications Forum of Japan

# **Revision History**

Ver.	Date	Chapter/Section	Reason	Revised Content
1.0	May 31, 2012	Establishment	Newly	
			established	

[Blank]

#### Introduction

This Guideline applies to the "700 MHz Band Intelligent Transport Systems Standard ARIB STD-T109" (hereinafter referred to as "the Standard"). It describes how to verify the connectivity, security, and interoperability of land mobile stations for systems using the Standard. The Guideline covers test items, procedures, and specifications of testing equipment. The Guideline is intended to ensure interoperability of land mobile radio stations (hereinafter referred to as "mobile stations") implementing the Standard, and to promote the spread of 700 MHz band intelligent transport systems.

#### (1) Background

Since 2009, the Committee for the Realization of Driver Assistance Communications Systems has been placing a major focus on the 700 MHz band for the implementation of a driver assistance communications system, and has been exploring topics such as interoperability, operations management, and security.

#### (2) Purpose

This Guideline is intended to prevent a situation where different manufacturers of mobile stations interpret the Standard differently, leading to a failure to connect. For this purpose, the Guideline describes how to check the basic communication characteristics of mobile stations to verify connectivity between mobile stations from different manufacturers, and to make sure that a given level of performance is provided.

[Blank]

# Interoperability Verification Guideline

### Contents

Chapter 1 General Descriptions	1
1.1 Overview	1
1.2 Test implementation	1
1.3 Normative references	1
1.4 Items not covered in the Guideline	2
1.5 Notation for numerals	2
Chapter 2 Connectivity Verification Test	3
2.1 Purpose of connectivity verification test	3
2.2 Preconditions	3
2.3 Configuration for connectivity verification test	3
2.3.1 Test configuration of technical condition for radio equipment	3
2.3.2 Test configuration of physical layer	3
2.3.3 Test configuration of communication control system	4
2.4 Test items for connectivity verification test	4
2.4.1 Test items of technical condition for radio equipment	4
2.4.2 Test items of physical layer	5
2.4.3 Test items of communication control system	5
2.5 Test description for connectivity verification test	7
2.5.1 Test description of technical condition for radio equipment	7
2.5.2 Test description of physical layer	7
2.5.3 Test description of communication control system	8
Chapter 3 Security Testing	11
3.1 Purpose of security testing	11
3.2 Configuration for security testing	11
3.3 Security testing items	13
3.4 Security testing description	15
3.5 Security testing procedure	19
Chapter 4 Interoperability Verification Test	21
4.1 Purpose of interoperability verification test	21
4.2 Configuration of interoperability verification test	21
4.2.1 Configuration for Interoperability test	21

4.2.2 Configuration for Conformance test, Performance test, and Exception test	st . 22
4.2.3 Sample test bed configuration	22
4.3 Interoperability verification test items	23
4.3.1 Interoperability verification test items	23
4.3.2 Interoperability verification test parameters	25
4.3.3 Interoperability verification test description	27
Chapter 5 Simulator Specifications	47
5.1 General items	47
5.1.1 Standard to follow	47
5.1.2 Reference standards	47
5.1.3 Compliance certifications to obtain (recommended)	48
5.1.4 Items not explicitly stated	48
5.2 System configuration	48
5.2.1 Test system configuration and simulator positioning	48
5.2.2 Interface points	48
5.2.3 Interface types	49
5.3 Equipment configuration and structure	49
5.3.1 Equipment configuration	49
5.3.2 General items	49
5.3.3 Description of equipment	50
5.3.4 Operation environment ratings (recommended)	50
5.3.5 Electrical specifications (recommended)	50
5.3.6 RF input	51
5.3.7 Reference signal	51
5.3.8 Trigger signal	51
5.4 Major functions	53
5.4.1 Mobile station functions	53
5.4.2 Base station functions	61
5.4.3 Test programs	64
5.4.4 Error handling function	65
5.5 Maintenance management function	65
5.5.1 Self-diagnosis function	65
5.5.2 Monitor terminal	66
5.5.3 Log data storage function	66
Chanter 6 Definitions and Abbreviations	67

	6.1 Glossary	. 67
	6.2 Abbreviations	. 7C
Α	nnex A: Values Determined by Operation Management Organization	. 75
Α	nnex B: Simulator Output Levels for Tests TR 2-2-4/TR 2-2-5	. 76

[Blank]

#### Chapter 1 General Descriptions

#### 1.1 Overview

Comfirming connectivity to land mobile station compliant with "700 MHz Band Intelligent Transport Systems Standard ARIB STD-T109" (hereinafter referred to as the "Standard") can be checked by testing the items listed in the ARIB Technical Report "700 MHz Band Intelligent Transport Systems Test Items and Conditions for Mobile Station Compatibility Confirmation ARIB TR-T20" (hereinafter referred to as "Technical Report"). However, it is important to check not only for connectivity to testing equipment but also for interoperability between mobile stations from different manufacturers.

Chapter 2 of this Guideline deals with test items that are not listed in the Technical Report but for which is desirable to perform practical testing. The chapter describes the connectivity verification items along with suitable test procedures. Chapter 3 describes security related test items and procedures, which are outside the scope covered by the Standard and the Technical Report. Chapter 4 describes test items and procedures for verifying interoperability between mobile stations from different manufacturers. Chapter 5 describes the specifications of a simulator designed to be used as connectivity testing equipment.

#### 1.2 Test implementation

This Guideline assumes that all operation testing based on the Standard has been performed by the mobile station manufacturer at the development or manufacturing stage.

The testing procedures described in this Guideline are designed to be able to be performed in a general testing environment, so that no special demands are placed on the testing entity or the manufacturer with regard to environmental conditions or special functions for the mobile station.

#### 1.3 Normative references

Items not specifically described in this Guideline are to be dealt with in accordance with the following standards. The version to use unless otherwise specified is the latest version.

ARIB STD-T109 700 MHz Band Intelligent Transport Systems Standard

ARIB TR-T20 700 MHz Band Intelligent Transport Systems Test Items and

#### Conditions for Mobile Station Compatibility Confirmation

#### 1.4 Items not covered in the Guideline

Numeric values or parameters not given in this Guideline are to be decided by the body responsible for system operation (hereinafter referred to as "operation management organization"). Specifics are provided in Annex A.

#### 1.5 Notation for numerals

This Guideline uses an appended "h" to denote hexadecimal numbers (i.e. "00h"), "b" to denote binary numbers (i.e. "00b"), and no indication for decimal numbers (i.e. "0").

#### Chapter 2 Connectivity Verification Test

#### 2.1 Purpose of connectivity verification test

The purpose of testing the connectivity of mobile stations is to verify that the manufacturer of the mobile station is meeting the specification requirements for mobile stations given in the Standard. To fulfill this purpose, two types of tests are required.

1: Using a connectivity measurement setup (measuring equipment and simulator), the mobile station is to be tested to establish that it meets the requirements laid down in the above Standard. 2: Interoperability with mobile stations from other manufacturers is to be tested.

This chapter describes the procedures for item 1. Item 2 is dealt with in Chapter 4 "Interoperability Verification Test".

#### 2.2 Preconditions

The connectivity verification test is to be implemented by the manufacturer of the mobile station on its own initiative. The test procedure, items, and test content are to be based on the Technical Report which is to be used as reference.

The current chapter provides supplementary information to the Technical Report.

#### 2.3 Configuration for connectivity verification test

#### 2.3.1 Test configuration of technical condition for radio equipment




Fig. 2-1 Test Configuration of Technical Condition for Radio Equipment

#### 2.3.2 Test configuration of physical layer

Identical to test configuration of technical condition for radio equipment described in section 2.3.1.

#### 2.3.3 Test configuration of communication control system




Fig. 2-2 Test Configuration of Communication Control System

2.4 Test items for connectivity verification test
Test items in this chapter are numbered using the following format: TR X-X-X.

#### 2.4.1 Test items of technical condition for radio equipment

Table 2-1 Test Items of Technical Condition for Radio Equipment

Test No.	Item
TR 1-1	Transmitter
TR 1-1-1	Frequency deviation
TR 1-1-2	Occupied bandwidth
TR 1-1-3	Antenna power tolerance
TR 1-1-4	Unwanted emission intensity
TR 1-1-5	Transmission data rate
TR 1-2	Receiver
TR 1-2-1	Limits of incidentally produced radiation
TR 1-3	Controller
TR 1-3-1	Interference prevention function
TR 1-3-2	Carrier sense function
TR 1-3-3	Timestamp control function

## 2.4.2 Test items of physical layer

Table 2-2 Test Items of Physical Layer

Test No.	Item
TR 2-1-1	Modulation accuracy
TR 2-1-2	Reception sensitivity
TR 2-1-3	Maximum input power for reception
TR 2-1-4	Blocking characteristics
TR 2-1-5	CCA sensitivity (preamble detection)
TR 2-1-6	CCA sensitivity (power detection)

# 2.4.3 Test items of communication control system

Table 2-3 Test Items of Communication Control System

Test No.	Item					
TR 2-2	Operation principle test					
TR 2-2-1	Mobile station signal reception					
TR 2-2-2	CSMA send check (data rate change)					
TR 2-2-3	CSMA send check (frame length change)					
TR 2-2-4	CSMA send check (distributed space)					
TR 2-2-5	CSMA send test (random waiting period)					
TR 2-2-6	CSMA send test (latest MSDU send)					
TR 2-2-7	Base station signal reception					
TR 2-2-8	Synchronization information update by base station signal					
TR 2-2-9	Timestamp update by base station signal					
TD 2 2 10	Roadside-to-vehicle communication period information update by					
TR 2-2-10	base station signal					
TR 2-2-11	Synchronization information update by mobile station signal					
TR 2-2-12	Timestamp update by mobile station signal					
TR 2-2-13	Roadside-to-vehicle communication period information update by					
IK 2-2-13	mobile station signal					
TR 2-2-14	Synchronization information check by elapsed time					
TR 2-2-15	Roadside-to-vehicle communication period information update by					
IK Z-Z-15	elapsed time					
TR 2-2-16	Inter-vehicle and roadside-to-vehicle communication layer check					
TR 2-3	Applied operation test					

TR 2-3-1	Synchronization information update by base station and mobile station signal
TR 2-3-2	Timestamp update by base station and mobile station signal
TR 2-3-3	Synchronization information update by multiple mobile station signals
TR 2-3-4	Timestamp update by multiple mobile station signals
TR 2-3-5	Roadside-to-vehicle communication period information update by multiple mobile station signals

- 2.5 Test description for connectivity verification test
- 2.5.1 Test description of technical condition for radio equipment

See section 2.4.1 of Technical Report. No additions.

#### 2.5.2 Test description of physical layer

See section 2.4.2 of Technical Report. Additional information is given for each test number below.

Test No. TR 2-1-3

Item Maximum input power for reception

Additions

[Test procedure]

- Adjust step attenuator so that signal from vector signal generator is x dBm (power exceeding -20 dBm) at antenna terminal of UUT (Unit Under Test). (Note 1)
- 5. Then adjust step attenuator so that signal from vector signal generator is -20 dBm at antenna terminal of UUT, and measure packet error rate [%] with packet error rate counter.

Note 1: Value of x to be specified by operation management organization.

Test No. TR 2-1-4

Item Blocking characteristics

Additions

[Test procedure]

- 11. Output a modulated signal corresponding to a 12 Mbps data rate from vector signal generator 1.
- 12. Perform test steps 2 to 10.

Test No. TR 2-1-5

Item CCA sensitivity (preamble detection)

Additions

[Test procedure]

- 7. Output a modulated signal corresponding to a 12 Mbps data rate from the vector signal generator.
- 8. Perform test steps 2 to 6.

Test No. TR 2-1-6

Item CCA sensitivity (power detection)

Additions

[Check items]

• Verify that power checked with signal analyzer in test step 4 is not observed in test step 6.

#### 2.5.3 Test description of communication control system

See section 2.4.3 of Technical Report. Additional information is given for each test number below.

Test No. TR 2-2-1

Item Mobile station signal reception

Additions

[Check items]

• Verify that content of simulator transmission ASDU and UUT reception ASDU matches.

Test No. TR 2-2-2

Item CSMA send check (data rate change)

Additions

[Check items]

· Verify that content of UUT transmission ASDU and simulator reception ASDU matches.

Test No. TR 2-2-6

Item CSMA send test (latest MSDU send)

Additions

[Check items]

 Verify that content of second UUT transmission ASDU and simulator reception ASDU matches.

Test No. TR 2-2-7

Item Base station signal reception

Additions

[Test conditions]

· When connectivity testing equipment is transmitting for multiple roadside-to-vehicle

communication periods, ensure that transmission is not performed outside of roadside-to-vehicle communication period.

Data rate ASDU data length Transmission count

12 Mbps 1500 octets (Note 3) 9 (Note 3)

Note 3: To be specified by operation management organization if secure communication is used.

#### [Check items]

- Verify that number of frames transmitted by connectivity testing equipment and number of frames received by the UUT matches.
- Verify that content of connectivity testing equipment transmission ASDU and UUT reception ASDU matches.

[Blank]

#### Chapter 3 Security Testing

#### 3.1 Purpose of security testing

The security testing procedures described in this Guideline are intended to verify that the mobile station is manufactured in such a way as to allow implementation of features based on security policy specified for the 700 MHz band intelligent transport system. Detailed testing of the actual security implementation is therefore outside the scope of this Guideline.

#### 3.2 Configuration for security testing

The physical configuration for security testing is the same as the configuration described in Chapters 2 and 4. The logical configuration for security testing consists of the security test scheme for inter-vehicle communication shown in Fig. 3-1 and the security test scheme for roadside-to-vehicle communication shown in Fig. 3-2. The test program is to be installed on the UUT, standard mobile station, standard base station, and simulator, and/or any additional external equipment. "Test program" refers to a program that is able create test messages, issue instructions for transmitting and acquiring such messages, display the test results and perform result evaluation as required. Test messages consist of security parameter information, application data, and other elements necessary for performing security testing. The standard mobile station is to be produced by each respective manufacturer and must be certified by the operation management organization. The standard base station is assumed to be a licensed station for which connectivity standards have been established by the operation management organization.




Fig. 3-1 Security Test Scheme for Inter-Vehicle Communication




Fig. 3-2 Security Test Scheme for Roadside-to-Vehicle Communication

# 3.3 Security testing items

# (1) Proposed test items for UUT

No.	Target	Tested section	Item	Details	NOTE
	Mobile station			Send short data frame (no	
		MS (UUT) →	Inter-vehicle	encryption)	
1			message transmission	Send short data frame (with	
'		SMS		encryption)	
				Check input/output encryption	
				function	
				Receive short data frame (no	
		CMC MC	Inter-vehicle	encryption)	
2	Mobile	SMS→MS	communication	Receive short data frame (with	
	station	(UUT)	message reception	encryption)	
				Check input/output encryption function	
				Receive short data frame (no	
				encryption)	
				Receive short data frame (with	
				encryption)	
	Mobile	SBS→ MS	Roadside-to-vehicl e communication message reception	Receive long data frame (no	
3	station	(UUT)		encryption)	
		(661)		Receive long data frame (with	
				encryption)	
				Check input/output encryption	
				function	
				Check security function with input of	
			Inter-vehicle	short data outside security	
4	Mobile	MS (UUT) →	communication	parameter range (no encryption)	
	station	SMS	invalid message	Check security function with input of	
			transmission	short data outside security	
				parameter range (with encryption) Check security function with	
		$\begin{array}{ll} \text{obile} & \text{MS (Sim.)} \rightarrow \\ \text{ation} & \text{MS (UUT)} \end{array}$	Inter vehicle	reception of short data with invalid	
	Mobile		Inter-vehicle communication	frame (no encryption)	
5	station		invalid message	Check security function with	
			reception	reception of short data with invalid	
				frame (with encryption)	
				Check security function with	
				reception of short data with invalid	
				frame (no encryption)	
				Check security function with	
			Roadside-to-vehicl	reception of short data with invalid	
6	Mobile	BS (Sim.) →	e communication	frame (with encryption)	
	station	MS (UUT)	invalid message	Check security function with	
			reception	reception of long data with invalid	
				frame (no encryption)	
				Check security function with	
				reception of long data with invalid	
				frame (with encryption)	

Note: "Short data" refers for example to a message with an ASDU length of 100 octets.

"Long data" refers for example to a message with an ASDU length of 1500 octets.

#### Legend

- · SMS: Standard mobile station
- · SBS: Standard base station
- MS (UUT): Mobile station under test
- · MS (Sim.): Mobile station simulated by simulator
- · BS (Sim.): Base station simulated by simulator

## 3.4 Security testing description

No.	1	Item	Inter-ve	hicle communication message transmission						
Test	Check that inter-vehicle communication message transmission is possible.									
outline										
Test	UUT → Standard mobile station									
conditions	With encry	/ption/\	Without e	ncryption						
Test	1. Test p	orogran	n for mo	obile station issues instruction to UUT to						
procedure	transm	nit mess	sage fram	ne.						
	2. Standa	ard mo	bile stati	on receives signal output by UUT and test						
	progra	m for n	nobile sta	ation extracts message from received frame.						
	Test value	patteri	า							
		Item		Test value						
	ASDU len	igth		100 octets						
	Security	parame	ter	Value x determined by operation						
				management organization						
	Encryptio	n		Yes/No (Note 1) (Note 2)						
	Note 1: If	f the U	UT imple	ements several encryption methods, the test						
	sho	ould be	performe	ed for each method.						
	Note 2: The test should be performed repeatedly using several different									
	end	cryption	ı keys.							
Verification	Message input to UUT and message obtained by standard mobile									
item	station must match.									

No.	2	Item	Inter-ve	ehicle cor	nmı	inication me	ssage re	eception		
Test	Check that inter-vehicle communication message reception is possible.									
outline										
Test	Standard	Standard mobile station → UUT								
conditions	With encr	With encryption/Without encryption								
Test	1. Test	program	n for mo	obile sta	tion	issues inst	ruction	to standard		
procedure	mobile	e station	to trans	mit mess	sage	frame.				
	2. UUT r	eceives	signal o	output b	y st	andard mol	oile sta	tion and test		
	progra	am for n	nobile sta	ition extr	acts	message fr	om rece	eived frame.		
	Test value	e patter	n							
		Item				Test val	ue			
	ASDU lei	ngth		100 oct	ets					
	Security	parame	eter	Value	Χ	determined	d by	operation		
				manage	eme	nt organizati	on			
	Encryption	on		Yes/No	(No	te 1)				
	Note 1: If the UUT implements several encryption methods, the test									
	should be performed for each method.									
Verification	Message input to standard mobile station and message obtained by									
item	UUT m	nust mat	tch.							

		l							
No.	3	Item	Roadside	e-to-vehicle communication message reception					
Test	Check <sup>-</sup>	Check that roadside-to-vehicle communication message reception is							
outline	possible	e.							
Test	Standar	d base s	tation →	UUT					
conditions	With end	cryption	/Without e	encryption					
Test	1. Base	station	test progr	ram issues instruction to standard base					
procedure	statio	on to tra	nsmit me	ssage frame.					
	2. UUT	receives	signal ou	tput by standard base station and test					
	prog	ram for	mobile sta	ation extracts message from received frame.					
	Test value pattern								
	Item Test value								
	ASDU length 100 octets / 1500 octets								
	Security parameter Value x determined by operation								
				management organization					
	Encryp	tion		Yes/No (Note 1)					
	Note 1:	If the U	JT implem	nents several encryption methods, the test					
	should be performed for each method.								
Verification	• Mess	age inpu	ut to stand	lard base station and message obtained by					
item	UUT must match.								

4	Item	Inter-vehicle	communication invalid message transmission				
Che	eck that	mobile station	n performs suitable error processing and				
operation is not interrupted when an input outsize security parameter							
range occurs.							
UUT	→ Stan	dard mobile s	tation				
With	encrypt	ion/Without e	encryption				
1. To	est prog	ram for mobil	le station issues instruction to UUT to				
tr	ansmit	message fram	ne with out-of-range security parameter.				
2. S	tandard	mobile statio	n receives signal output by UUT and test				
р	rogram	for mobile sta	ition extracts message.				
3. To	est prog	ram for mobil	le station issues instruction to UUT to				
tr	ansmit	message fram	ne with in-range security parameter.				
4. S	tandard	mobile statio	n receives signal output by UUT and test				
-	-		ition extracts message.				
Test value pattern							
			Test value				
			100 octets				
Sec	urity pa	rameter	Value x determined by operation				
			management organization				
			Yes/No (Note 1)				
Note 1: If the UUT implements several encryption methods, the test							
<ul> <li>should be performed for each method.</li> <li>If transmission with out-of-range security parameter is performed,</li> </ul>							
standard mobile station must not receive frame. (No signal output							
			range security parameter is performed,				
			n must receive frame, and message input to				
			ined by standard mobile station must match.				
	Che ope ran UUT With  1. T tr 2. S p 3. T tr 4. S p Test  Sec  Enc Note  • If st	Check that operation is range occu  UUT → Stan  With encrypt  1. Test progetransmit  2. Standard program  3. Test progetransmit  4. Standard program  Test value particular program  Test value particular program  Test value particular program  Test value particular program  It ASDU lengt  Security particular program  Test value particular program  Test value particular program  It ASDU lengt  Security particular program  Test value particular program  It ASDU lengt  Security particular program  Test value particular program  It ASDU lengt  Security particular program  Test value par	Check that mobile station operation is not interrupt range occurs.  UUT → Standard mobile station with encryption/Without encryption/Without encryption/Without encryption/Without encryption/Without encryption/Without encryption for mobile station program for mobile station for mobile station station with our standard mobile station from UUT)  • If transmission with instandard mobile station standard mobile standard mobile station standard mobile standard mo				

No.	5 Item	Inter-vehicle communication invalid message reception					
Test	Check that mobile station performs suitable error processing and						
outline	operation is not interrupted when invalid frame signal occurs.						
Test	Simulator → UUT						
conditions	With encryption	n/Without encryption					
	<ul> <li>Simulator m</li> </ul>	ust operate as mobile station.					
Test	1. Test progra	m for simulator issues instruction to simulator to					
procedure	transmit in	valid message frame (frame with out-of-range data					
	structure o	r frame created with out-of-range security parameter					
	setting).						
	2. UUT receiv	es signal output by simulator and test program for					
	mobile stat	ion extracts message from received frame.					
	3. Test progra	m for simulator issues instruction to simulator to					
	transmit no	ormal message frame.					
	4. UUT receiv	es signal output by simulator and test program for					
	mobile station extracts message from received frame.						
	Test value pat	tern					
	Item Test value						
	ASDU length	100 octets					
	Security parameter Value x determined by operation						
		management organization					
	Encryption Yes/No (Note 1)						
	Note 1: If the UUT implements several encryption methods, the test						
	should be performed for each method.						
Verification	UUT must not output message when invalid frame is sent.						
items	Alternatively, UUT may output an indication that an invalid message						
	frame is pr	ocessed.					
	If transmiss	sion with normal message frame is performed, UUT must					
	receive fran	me, and message input to simulator and message					
	obtained by	UUT must match.					

No.	6	Item	Roadside-to-vehicle communication invalid message				
			reception				
Test	Check that mobile station performs suitable error processing and						
outline	operation is not interrupted when invalid frame signal occurs.						
Test	Sim	ulator →	UUT				
conditions	With	encrypt	ion/Without e	encryption			
	·S	imulator	must operate	e as base station.			
Test	1. T	est prog	ram for simul	ator issues instruction to simulator to			
procedure	t	ransmit	invalid messa	ge frame (frame with out-of-range data			
	S	tructure	or frame crea	ated with out-of-range security parameter			
	S	etting).					
	2. L	JUT rece	ives signal ou	tput by simulator and test program for			
	r	nobile st	ation extracts	message from received frame.			
	3. T	est prog	ram for simul	ator issues instruction to simulator to			
			normal messa				
			_	tput by simulator and test program for			
				message from received frame.			
	Test	value p					
		It	em	Test value			
		DU lengt		100 octets / 1500 octets			
	Sec	curity pa	rameter	Value x determined by operation			
				management organization			
		ryption		Yes/No (Note 1)			
	Note 1: If the UUT implements several encryption methods, the test						
	should be performed for each method.						
Verification	UUT must not output message when invalid frame is sent.						
items				output an indication that an invalid message			
			processed.				
				rmal message frame is performed, UUT must			
				ssage input to simulator and message			
	0	btained	by UUT must	match.			

#### 3.5 Security testing procedure

When performing security testing, the following items must be as determined by the operation management organization.

- (1) Security related message configuration and format
- (2) Security related encryption key handling and processing method
- (3) Concrete values of security related parameters

[Blank]

#### Chapter 4 Interoperability Verification Test

#### 4.1 Purpose of interoperability verification test

The test is intended to prevent a situation where different manufacturers of mobile stations interpret the Standard differently, leading to a failure to connect. For this purpose, the test checks the basic communication characteristics of mobile stations to verify connectivity between mobile stations from different manufacturers, and to verify that a given level of performance is provided. Basic communication connectivity is checked with the Interoperability test. Compliance with standards, performance, and exception handling capability are checked with the Conformance test, Performance test, and Exception test.


#### 4.2 Configuration of interoperability verification test

There are two configurations for interconnectivity verification testing. One is used for the Interoperability test and the other for the Conformance, Performance, and Exception tests.

The Interoperability test configuration consists of the UUT and a standard mobile station produced by each manufacturer. The configuration for the Conformance test, Performance test, and Exception test consists of the UUT and a simulator that performs transmission and reception operation of a mobile station and base station. The simulator must incorporate an RF transmitter and receiver for both base station and mobile station operation and must be able to communicate with the UUT, but the concrete configuration and model type for simulator equipment are not covered by this Guideline. Specifications to ensure that the required functions are given in Chapter 5.

#### 4.2.1 Configuration for Interoperability test

The Interoperability test configuration consists of the UUT and a standard mobile station. An example for a test configuration designed to verify interoperability by radio connection is shown Fig. 4-1.



OUI : Unit Under Test

SMS: Standard Mobile Station

Fig. 4-1 Test Configuration for Interoperability by Radio Connection

#### 4.2.2 Configuration for Conformance test, Performance test, and Exception test

The configuration for the Conformance test, Performance test, and Exception test consists of the UUT and connectivity testing equipment. The connectivity testing equipment is a simulator that can perform the transmission and reception functions of a mobile station and base station. For this purpose, it is equipped with an RF transmitter/receiver for both mobile station and base station operation, allowing two-way communication with the UUT. The UUT and connectivity testing equipment may be connected either by radio connection via antennas on both sides or by wired connection using coaxial cable or similar. The configuration is shown in Fig. 4-2.




Fig. 4-2 Test Configuration for Conformance, Performance, and Exception by Radio Connection

#### 4.2.3 Sample test bed configuration

When performing the interoperability verification test, it is desirable to use a

dedicated test bed that easily allows establishing the required test configuration. An example for such a test bed comprising the simulator, standard base station, standard mobile station, computer for performing analysis, etc. is shown in Fig. 4-3.




Fig.4-3 Sample Test Bed Configuration

#### 4.3 Interoperability verification test items

#### 4.3.1 Interoperability verification test items

The interoperability test items are listed in Table 4-1. A check mark ( $\checkmark$ ) is used to indicate to which test category (IN: Interoperability, CON: Conformance, PER: Performance, EX: Exception) the respective item belongs.

		Table 4-1 Interoperabil	ity verifica	tion rest recins	•			
No.	Layer	Item	Applicable standard	NOTE	IN	CON	PER	EX
1-1	LLC transmission	Address field	4.3.5.6.1	=AAAAh		V		
1-2		Control field	4.3.5.6.2	=03h		レ		
1-3		Protocol identifier	4.3.5.6.3	=03 0000 0001h		レ		
1-4	LLC reception	Address field	4.3.5.5.2	Operation other than AAAAh undefined				レ

Table 4-1 Interoperability Verification Test Items

				Discarded or		
1-5		Control field	4.3.5.5.3	passed to higher layer with identifier code if non-number type information (UI) command		ν
				(P bit) is 1 (13h) Operation other		
1-6		Protocol identifier	1	than 03 0000 0001h undefined		レ
1-7		PDU with invalid LLC	4.3.5.3.2	Invalid for L1/MAC sublayer, PDU length not integer multiple of octets, PDU length less than 8 octets, no valid control field		L
2-1	IR transmission	Protocol version number	4.4.3.1.2	=0000b	レ	
2-2		Туре	1	=0000b	レ	
2-3		Reserved	<u> </u>	=0b	レ	
2-4		Enhanced field	<u> </u>	=00h	レ	
2-5	IR reception	Protocol version number	4.4.3.3.2	Operation other than 0000b undefined		レ
2-6		Туре	1	Operation other than 0000b undefined		V
2-7		Synchronization information	1	Non-standard operation undefined		V
2-8		Reserved	1	Operation other than 0b undefined		V
2-9		Timestamp	1	Non-standard operation undefined		レ
2-10		Roadside-to-vehicle communication period length	1	Non-standard operation undefined		V
2-11		Enhanced field	1	Operation other than 00h undefined		レ
3-1	L7 transmission	Link address	4.5.2.1.4	= MAC control field	レ	
			4.5.3.1.2	Destination address		
3-2		Version	1	0	レ	
3-3		Security classification information	1	Security Information	レ	
3-4		Reserved	1	0	レ	
3-5		Application associated information	1	Application Associated Information	レ	
3-6	L7 reception	Link address	4.5.2.1.4	Identification Code specified in MAC control field	レ	
			4.5.3.2.2			

3-7		Security classification information	1			レ		
3-8		Application associated information	1			レ		
3-9		Application data length	1	0 - 1500 octets, out-of-range reception undefined				レ
4-1	Apps transmission	Application message	-	Application message transmission	レ			
4-2		High-load environment (inter-vehicle)	-				V	
4-3		High-load environment (inter-vehicle + roadside-to-vehicle)	-				レ	
4-4	Apps reception	Application message	-	Application message reception	レ		レ	
4-5		Difficult reception environment	-				$\nu$	

# 4.3.2 Interoperability verification test parameters

### 4.3.2.1 Layer 1

The test parameters for layer 1 are as follows.

Parameter	Value			
Output power	At antenna terminal of UUT: -50 dBm			
Data rate	Mobile station: 6 Mbps, Base station: 12 Mbps			

### 4.3.2.2 Layer 2

The test parameters for layer 2 are as follows.

Parameter	Value
Destination address	FFFF FFFF FFFFh (default), FE00 0000 0000h
Transmission source	[Arbitrary value]
address	
Radio station	[Equipment-specific value]
identification code	
Transmission count value	[Arbitrary value]

### 4.3.2.3 LLC

The LLC related test parameters are as follows. (Underlined are exception values)

Parameter	Value	
DSAP/SSAP field	AAAAh (default), <u>0000h</u>	
Control field	03h (default), <u>13h</u> , <u>FFh</u>	
Protocol identifier	03 0000 0001h (default), <u>00 0000 0800h</u>	
PDU length	96 (default), <u>0</u>	

4.3.2.4 Inter-vehicle and roadside-to-vehicle communication control information layer The parameters for the inter-vehicle and roadside-to-vehicle communication control information layer are as follows. (Underlined are exception values)

Parameter	Value
Version	0 (default), <u>1</u>
Туре	0 (mobile station default), 1 (base station default), 2
Synchronization	000b (default), <u>011b</u>
information	
Reserved	0 (default), <u>1</u>
Timestamp	0 (default), <u>1000000</u>
Roadside-to-vehicle	All periods: 00b (default)
communication	Period 1: 01b, Period 2: 02b, Other period: 00b
period information	
Transfer count	
Roadside-to-vehicle	All periods: 0 units (default),
communication	Period 1 to 15: 63 units, Period 16: 0 units,
period information	Period 1: 63 units, Period 2: 1 unit,
Roadside-to-vehicle	Other periods: 0 units
communication	
period length	
Enhanced field	00h (default), <u>FFh</u>

### 4.3.2.5 Layer 7

The test parameters for layer 7 are as follows. (Underlined are exception values)

(1) MobileStationBroadcastData primitive

Parameter	Value		
ControlInformation/DataRate	0		
SecurityClassification	0, 1 (selected according to security)		
ApplicationAssociatedInformation	0		
ApplicationDataLength	100 (default), 0, 1500, 1501		
ApplicationData	Value x *		
LinkAddress	FFFF FFFF FFFFh (default),		
	FE00 0000 0000h		

## $(2) Base Station Broad cast Data\ primitive$

Parameter	Value		
ControlInformation/DataRate	4		
SecurityClassification	0, 1 (selected according to security)		
ApplicationAssociatedInformation	00h (default), <u>FFh</u>		
ApplicationDataLength	1500 (default), 0, <u>1501</u>		
ApplicationData	Value x *		
LinkAddress	FFFF FFFF FFFFh		

<sup>\*:</sup> Value of x to be specified by operation management organization.

## 4.3.3 Interoperability verification test description

# 4.3.3.1 Test description for Interoperability test

No.	4-1-IN	Item	Apps tra	ansmission: Application message		
Test	Verify that application message transmission is possible.					
outline						
Test	UUT → S	Standard	mobile s	tation		
conditions	Encryptic	on key: v	alue x. V	alue of x to be specified by operation		
	manager	nent orga	anization			
Test	1. Test p	orogram 1	for mobil	e station issues instruction to UUT to		
procedure	transı	mit frame	e with pro	edetermined message.		
	2. Stanc	dard mobi	ile statio	n receives frame, and test program for		
	mobil	e station	extracts	message.		
	Test valu	ıe patterr	1			
		Item		Test value		
	ASDU	length		100 octets		
	Securi	ity param	eter	Value x determined by operation		
				management organization		
	Encry	otion		Yes/No (Note 1) (Note 2)		
	Note 1:	If the UU	T implen	nents several encryption methods, the test		
	!	should be	eperform	ned for each method.		
	Note 2: The test should be performed repeatedly using several					
		different	encryptic	on keys.		
Verification	<ul> <li>Messa</li> </ul>	age input	to UUT a	and message obtained by standard mobile		
item	station must match.					

No.	4-4-IN	Item	Apps red	ception: Application message		
Test	Verify that application message reception is possible.					
outline						
Test	Standar	d mobile s	station –	→ UUT		
conditions	Encrypti	on key: v	alue x. V	alue of x to be specified by operation		
	manage	ment orga	anization			
Test	1. Test	program	for mobil	e station issues instruction to standard		
procedure	mobi	le station	to trans	mit frame with predetermined message.		
	2. UUT	receives f	rame, ar	nd test program for mobile station extracts		
	mess	sage.				
	Test val	ue patterr	າ			
		Item		Test value		
	ASDL	J length		100 octets		
	Secui	ity param	neter	Value x determined by operation		
				management organization		
	Encry	ption		Yes/No (Note 1) (Note 2)		
	Note 1:	If the UU	T implen	nents several encryption methods, the test		
		should be	e perform	ned for each method.		
	Note 2: The test should be performed repeatedly using several					
	different encryption keys.					
Verification	<ul> <li>Mess</li> </ul>	age input	to stand	ard mobile station and message obtained by		
item	UUT must match.					

# 4.3.3.2 Test description for Conformance test

No.	1-1-CON	Item	LLC transmission:	Address field				
Test	Verify that transmission is performed with correct LLC header format.							
outline								
Test	UUT → Sin	nulator						
conditions	<ul> <li>Simulate</li> </ul>	or must	operate as mobile s	tation.				
Test	1. UUT ser	1. UUT sends arbitrary frame.						
procedure	2. Simulat	or receiv	ves frame.					
Verification	<ul> <li>Address</li> </ul>	field in	LLC control field of	received frame m	ust match			
item	specified bit string.							
	Verification item Standard value							
	DSAP/SSAP address field AAAAh							
1								

No.	1-2-CON	Item	LLC transmission:	Control field				
Test	Verify tha	Verify that transmission is performed with correct LLC header format.						
outline								
Test	UUT → Sin	nulator						
conditions	<ul> <li>Simulate</li> </ul>	or must	operate as mobile s	tation.				
Test	1. UUT ser	UUT sends arbitrary frame.						
procedure	2. Simulat	or receiv	ves frame.					
Verification	Control field in LLC control field of received frame must match							
item	specified bit string.							
	Verification item Standard value							
	Control field 03h							

No.	1-3-CON Item LLC transmission: Protocol identifier							
Test	Verify tha	Verify that transmission is performed with correct LLC header format.						
outline								
Test	$UUT \rightarrow Sim$	nulator						
conditions	<ul> <li>Simulato</li> </ul>	or must	operate as mobile s	tation.				
Test	1. UUT ser	UUT sends arbitrary frame.						
procedure	2. Simulat	or receiv	ves frame.					
Verification	<ul> <li>Protocol</li> </ul>	Protocol identifier in LLC control field of received frame must match						
item	specified	specified bit string.						
	Verification item Standard value							
	Protocol identifier 03 0000 0001h							

No.	2-1-CON	Item	IR transmission: F	Protocol version nun	nber		
Test	Verify tha	t transn	nission is performed	d with correct IR cor	ntrol field		
outline	format.						
Test	UUT → Sin	nulator					
conditions	<ul> <li>Simulate</li> </ul>	Simulator must operate as mobile station.					
Test	1. UUT sei	1. UUT sends arbitrary frame.					
procedure	2. Simulat	2. Simulator receives frame.					
Verification	Protocol version number in IR control field of received frame must						
item	match specified bit string.						
	Verification item Standard value						
	Protocol v	Protocol version number 0000b					

No.	2-2-CON	Item	IR transmission: Ty	<i>у</i> ре		
Test	Verify tha	t transn	nission is performed	with correct IR conti	rol field	
outline	format.					
Test	UUT → Sin	nulator				
conditions	<ul> <li>Simulate</li> </ul>	Simulator must operate as mobile station.				
Test	UUT sends arbitrary frame.					
procedure	2. Simulator receives frame.					
Verification	Type in IR control field of received frame must match specified bit					
item	strings.					
	Verification item Standard value					
	Type 0000b					

No.	2-3-CON	Item	IR transmission: Re	eserved		
Test	Verify tha	t transn	nission is performed	with correct IR contr	rol field	
outline	format.					
Test	UUT → Sim	nulator				
conditions	<ul> <li>Simulate</li> </ul>	Simulator must operate as mobile station.				
Test	1. UUT sends arbitrary frame.					
procedure	2. Simulator receives frame.					
Verification	Reserved field in IR control field of received frame must match					
item	specified bit strings.					
	Verification item Standard value					
	Reserved 0b					
					•	

No.	2-4-CON	Item	IR transmission: Enh	nanced field			
Test	Verify tha	t transn	nission is performed w	vith correct IR conti	rol field		
outline	format.						
Test	UUT → Sin	nulator					
conditions	<ul> <li>Simulate</li> </ul>	Simulator must operate as mobile station.					
Test	1. UUT sends arbitrary frame.						
procedure	2. Simulat	2. Simulator receives frame.					
Verification	Enhanced field in IR control field of received frame must match						
item	specified bit strings.						
	Verification item Standard value						
	Enhanced	Enhanced field 00h					

No.	3-1-CON	Item	L7 transmission: Link Address		
Test	Verify that	t LinkAc	ddress included in		
outline	MobileStat	tionBroa	adcastData.request which is a primitive between		
	application	n and la	yer 7 can provide MAC control field destination		
	address.				
Test	$UUT \rightarrow Sim$	nulator			
conditions	<ul> <li>Simulato</li> </ul>	Simulator must operate as mobile station.			
Test	1. Test program for mobile station issues instruction to UUT to				
procedure	transmit a frame with test value assigned to LinkAddress.				
	2. Simulator receives frame.				
	Test value pattern				
	Item Test value				
	LinkAddress FFFF FFFF FFFFh/FE00 0000 0000h				
			<u> </u>		
Verification	MAC control field destination address of received frame must match				
item	value as	signed	to LinkAddress.		

No.	3-2-CON	Item	L7 transmissio	n: Version			
Test	Verify tha	t transn	nission is perform	med with correct layer	7 header		
outline	format.						
Test	$UUT \to Sin$	nulator					
conditions	<ul> <li>Simulate</li> </ul>	Simulator must operate as mobile station.					
Test	1. UUT se	1. UUT sends arbitrary frame.					
procedure	2. Simula	2. Simulator receives frame.					
Verification	Layer 7 header version in received frame must match specified bit						
item	strings.						
	Ve	Verification item Standard value					
	Version	Version 0000b					

No.	3-3-CON	Item	L7 transmissio	n: Security classification information	on	
Test	Verify tha	t Securi	tyClassification	included in		
outline	MobileSta	tionBroa	adcastData.requ	est which is a primitive between		
	application	n and la	yer 7 can provid	de layer 7 header security		
	classificat	ion info	mation.			
Test	$UUT \rightarrow Sim$	nulator				
conditions	Simulator must operate as mobile station.					
Test	Test program for mobile station issues instruction to UUT to					
procedure	transmit a frame with test value assigned to SecurityClassification.					
	2. Simulat	2. Simulator receives frame.				
	Test value pattern					
	Item Test value					
	SecurityClassification 0/1					
Verification	Security classification information of layer 7 header in received					
item	frame m	nust ma	tch value assign	ed to SecurityClassification.		

No.	3-4-CON	Item	L7 transmission	n: Reserved		
Test	Verify tha	t transn	nission is perform	med with correct layer	7 header	
outline	format.					
Test	UUT → Sin	nulator				
conditions	<ul> <li>Simulate</li> </ul>	Simulator must operate as mobile station.				
Test	1. UUT sends arbitrary frame.					
procedure	2. Simulator receives frame.					
Verification	Layer 7 header reserved field in received frame must match					
item	specified bit strings.					
	Verification item Standard value					
	Reserved 000b					
		•			-	

No.	3-5-CON Item L7 transmission: Application associated information					
Test	Verify that ApplicationAssociatedInformation included in					
outline	MobileStationBroadcastData.request which is a primitive between					
	application and layer 7 can provide layer 7 header application					
	associated information.					
Test	UUT → Simulator					
conditions	Simulator must operate as mobile station.					
Test	Test program for mobile station issues instruction to UUT to					
procedure	transmit a frame with test value assigned to					
	ApplicationAssociatedInformation.					
	2. Simulator receives frame.					
	Test value pattern					
	Item Test value					
	ApplicationAssociatedInformation 00h/FFh					
Verification	Application associated information of layer 7 header in received					
item	frame must match value assigned to					
	ApplicationAssociatedInformation.					

No.	3-6-CON Item	L7 reception: Link Address			
Test	Verify that Link	address included in			
outline	MobileStationBr	padcastData.indication which is a primitive between			
	application and	ayer 7 allows obtaining MAC control field with radio			
	station identifica	tion code.			
Test	Simulator $\rightarrow$ UUT				
conditions	<ul> <li>Simulator mus</li> </ul>	t operate as mobile station.			
Test	Simulator transmits frame with test value assigned to radio station				
procedure	identification code in MAC control field.				
	2. UUT receives	rame, and test program for mobile station obtains			
	LinkAddress.				
	Test value patteri	1			
	Item	Test value			
	Radio station	[Equipment-specific value or			
	identification code arbitrary value]				
Verification	LinkAddress in obtained MobileStationBroadcastData.indication must				
item	match value assigned to radio station identification code in MAC				
	control field.				

No.	3-7-CON Item L7 reception: Security classification information					
Test	Verify that SecurityClassification included in					
outline	MobileStationBroadcastData.indication which is a primitive between					
	application and layer 7 can provide layer 7 header security					
	classification information.					
Test	Simulator → UUT					
conditions	<ul> <li>Simulator must operate as mobile station.</li> </ul>					
Test	Simulator transmits frame with test value assigned to security					
procedure	classification information in layer 7 header.					
	2. UUT receives frame, and test program for mobile station obtains					
	SecurityClassification.					
	Test value pattern					
	Item Test value					
	Security section information 0/1					
Verification	SecurityClassification in obtained					
item	MobileStationBroadcastData.indication must match value assigned					
	to Layer 7 header security classification information.					

No.	3-8-CON Item L7 reception: Application associated information					
Test	Verify that ApplicationAssociatedInformation included in					
outline	MobileStationBroadcastData.indication which is a primitive between					
	application and layer 7 can provide layer 7 header application					
	associated information.					
Test	Simulator → UUT					
conditions	Simulator must operate as mobile station.					
Test	1. Simulator transmits frame with test value assigned to application					
procedure	associated information in layer 7 header.					
	2. UUT receives frame, and test program for mobile station obtains					
	ApplicationAssociatedInformation.					
	Test value pattern					
	Item Test value					
	Application associated information 00h/FFh					
Verification	ApplicationAssociatedInformation in obtained					
item	MobileStationBroadcastData.indication must match value assigned to					
	layer 7 header application associated information.					

# 4.3.3.3 Test description for Performance test

No.	4-2-PER Item Apps transmission: High-load environment (inter-vehicle)								
Test outline	Verify that application message transmission is possible also under high reception load conditions.								
Test	UUT ⇔ Simulator								
conditions	Simulator must operate as mobile station.								
Test	1. Simulator repeats the following steps from transmission 1 to								
procedure	reception 2 in 200 ms intervals.								
	<ul><li>(1) Transmission 1: continuous send (from 0 to 92 ms) using [50 μ</li><li>+ x μs] frame interval</li></ul>	S							
	(2) Reception 1: (from 92 to 94 ms)								
	(3) Transmission 2: continuous send (from 94 to 198 ms) using [50 μs + x μs] frame interval								
	(4) Reception 2: (from 198 to 200 ms)								
	Value of x µs to be specified by operation management organization.								
	2. Test program for mobile station issues instruction to UUT to								
	transmit one message frame every 100 ms. Repeat up to a count of 1000.								
	3. Simulator receives frames. Count number of received frames.								
Verification item	<ul> <li>At least x frames must be normally received by simulator. Value of x to be specified by operation management organization.</li> </ul>	;							

No.	4-3-PER Item Apps transmission: High-load environment									
	(inter-vehicle + roadside-to-vehicle)									
Test	Verify that application message transmission is possible also under									
outline	high reception load conditions.									
Test	UUT ⇔ Simulator									
conditions	<ul> <li>Simulator must operate as base station and mobile station.</li> </ul>									
Test	Simulator repeats the following steps from transmission 1 to									
procedure	reception 2 in 200 ms intervals.									
	(1) Transmission 1:									
	<ul> <li>Roadside-to-vehicle communication message</li> </ul>									
	Send one frame with ASDU length of 1500 octets within each									
	roadside-to-vehicle communication period (from 0 to 3.024 ms,									
	6.240 to 9.264 ms, 12.480 to 15.504 ms, 18.720 to 21.744 ms,									
	24.960 to 27.984 ms, 31.200 to 34.224 ms, 37.440 to 40.464									
	ms, 43.680 to 46.704 ms, 49.920 to 52.944 ms, 56.160 to									
	59.184 ms, 62.400 to 65.424 ms, 68.640 to 71.664 ms, 74.880									
	to 77.904 ms, 81.120 to 84.144 ms, 87.360 to 90.384 ms)									
	<ul> <li>Inter-vehicle communication message</li> </ul>									
	Using [50 µs + x µs] transmission frame interval, from 0 to 92									
	ms, except during roadside-to-vehicle communication period									
	(2) Reception 1: (from 92 to 94 ms)									
	(3) Transmission 2:									
	<ul> <li>Roadside-to-vehicle communication message</li> </ul>									
	Send one frame with ASDU length of 1500 octets within each									
	roadside-to-vehicle communication period (from 100 to 103.024									
	ms, 106.240 to 109.264 ms, 112.480 to 115.504 ms, 118.720 to									
	121.744 ms, 124.960 to 127.984 ms, 131.200 to 134.224 ms,									
	137.440 to 140.464 ms, 143.680 to 146.704 ms, 149.920 to									
	152.944 ms, 156.160 to 159.184 ms, 162.400 to 165.424 ms,									
	168.640 to 171.664 ms, 174.880 to 177.904 ms, 181.120 to									
	184.144 ms, 187.360 to 190.384 ms)									
	<ul> <li>Inter-vehicle communication message</li> </ul>									
	Using [50 µs + x µs] transmission frame interval, from 94 to 198									
	ms, except during roadside-to-vehicle communication period.									
	(4) Reception 2: (from 198 to 200 ms)									
	Value of x µs to be specified by operation management organization.									
	2. Test program for mobile station issues instruction to UUT to transmit									
	one message frame every 100 ms. Repeat up to a count of 1000.									
	3. Simulator receives frames. Count number of received frames.									
Verification	At least x frames must be normally received by simulator. Value of									
item	x to be specified by operation management organization.									

No.	4-4-PER Item Apps reception: Application message								
Test	Verify that application message reception is possible also under high								
outline	reception load conditions.								
Test	Simulator → UUT								
conditions	Simulator must operate as mobile station.								
Test	1. Simulator performs continuous send in 100 ms units, using [50 μs								
procedure	+ x μs] transmission frame interval. Value of x μs to be specified by								
	operation management organization.								
	2. UUT receives frames, and test program for mobile station extracts								
	messages. Count number of received messages.								
Verification	At least x messages must be extracted by test program for mobile								
item	station for every 100 ms. Value of x to be specified by operation								
	management organization.								

No.	4-5-PER Item Apps reception: Difficult reception environment								
Test outline	Verify that application message reception is possible also under high reception load conditions, when reception is temporarily difficult.								
Test	<ul> <li>Establish a configuration as shown below.</li> <li>Simulator must operate as mobile station.</li> <li>Vector signal generator must operate as mobile station.</li> <li>Simulator and vector signal generator must be synchronized by synchronizing signal.</li> <li>Input levels to UUT from simulator and vector signal generator must be identical.</li> </ul> Simulator Synchronizing Signal								
Test procedure	<ol> <li>Simulator performs continuous send, using [50 µs + x µs] transmission frame interval. Value of x µs to be specified by operation management organization.</li> <li>Vector signal generator performs continuous send, using 2 ms transmission frame interval.</li> <li>UUT sends frames, and test program for mobile station extracts messages. Number of messages for an arbitrary 100 ms period are counted.</li> <li>Repeat steps 1 to 3 x times, changing transmission start timing for vector signal generator every time. Average of message count for x times is determined. Value of x to be specified by operation management organization.</li> </ol>								
Verification item	At least x messages must be extracted by test program for mobile station for every 100 ms. Value of x to be specified by operation management organization.								

# 4.3.3.4 Test description for Exception test

No.	1-4-EX	Item	LLC reception	n: Invalid address field					
Test	Verify that no malfunction occurs when a frame with a non-standard								
outline	address	field in	LLC control fi	eld is received.					
Test	Simulator	· → UU1	Γ						
conditions	• Simula	itor mus	st operate as	mobile station.					
Test	1. Simula	ator sen	ds frames wit	h test values assigned to address fi	eld in				
procedure	LLC co	ontrol fie	eld, in the ord	er (1), (2).					
	2. UUT re	2. UUT receives frames, and test program for mobile station is used to							
	check	messag	jes.						
	Test value	e patter	n						
		Iter	n	Test value					
	DSAP/S	DSAP/SSAP address field (1) 0000h (non-standard value)							
	(2) AAAAh (standard value)								
Verification	Verify that frames with standard values are received normally and								
item	messages can be extracted.								

No.	1-5-EX Item LLC reception: Invalid control field								
Test	Verify that no malfunction occurs when a frame with a non-standard								
outline	control field in LLC control field is received.								
Test	Simulator	r → UUT	-						
conditions	• Simula	ator mus	t operate as mobile station.						
Test	1. Simul	ator sen	ds frames with test values assigned to control field in						
procedure	LLC co	ontrol fie	eld, in the order (1), (2), (3).						
	2. UUT r	2. UUT receives frames, and test program for mobile station is used to							
	check	messag	es.						
	Test valu	e patteri	n						
		Item	Test value						
	Control	field	(1) FFh (non-standard value)						
			(2) 13h (non-standard value)						
		(3) 03h (standard value)							
Verification	<ul> <li>Verify that frames with standard values are received normally and</li> </ul>								
item	messa	ages can	be extracted.						

No.	1-6-EX Item LLC reception: Invalid protocol identifier								
Test	Verify that no malfunction occurs when a frame with a non-standard								
outline	protocol	identifi	fier in LLC control field is received.						
Test	Simulator	- → UU7	JT						
conditions	<ul> <li>Simula</li> </ul>	tor mus	ust operate as mobile station.						
Test	1. Simula	ator sen	nds frames with test values assigned to protocol						
procedure	identif	fiers in L	LLC control field, in the order (1), (2).						
	2. UUT receives frames, and test program for mobile station is used to								
	check	check messages.							
	Test value	e patter	rn						
		Item	Test value						
	Protoco	l identifi	fier (1) 00 0000 0800h (non-standard value)						
	(2) 03 0000 0001h (standard value)								
Verification	Verify that frames with standard values are received normally and								
item	messages can be extracted.								

No.	1-7-EX Item LLC reception: PDU with invalid LLC								
Test outline	Verify that received frames with non-standard LLC Protocol Data Unit (LPDU) are discarded properly.								
Test conditions	Simulator → UUT  • Simulator must operate as mobile station.								
Test procedure	in the 2. UUT re check	<ol> <li>Simulator sends frames with test values set as PDU length of LLC, in the order (1), (2).</li> <li>UUT receives frames, and test program for mobile station is used to check messages.</li> <li>Test value pattern</li> </ol>							
	PDU ler	PDU length  (1) 0 octets (out-of-range value)  (2) 96 octets (in-range value)							
Verification item	<ul> <li>Verify that frames with out-of-range values are not received, and frames with in-range values are received normally and messages can be extracted.</li> </ul>								

No.	2-5-EX	2-5-EX Item IR reception: Invalid protocol version number							
Test	Verify that no malfunction occurs when a frame with a non-standard								
outline	protocol	version	number in	IR c	control field is received.				
Test	Simulator	· → UU1	Γ						
conditions	<ul> <li>Simula</li> </ul>	itor mus	st operate a	is mo	obile station.				
Test	1. Simula	ator sen	ds frames v	with	test values assigned to protocol				
procedure	versio	n numb	ers in IR co	ntro	I field, in the order (1), (2).				
	2. UUT re	2. UUT receives frames, and test program for mobile station is used to							
	check	check messages.							
	Test value	e patter	n						
		Item			Test value				
	Protoco	I version	n number	(1)	0001b (non-standard value)				
	(2) 0000b (standard value)								
Verification	Verify that frames with standard values are received normally and								
item	messa	ges can	be extract	ed.					

No.	2-6-EX Item IR reception: Invalid type								
Test	Verify that no malfunction occurs when a frame with non-standard								
outline	type in	R contro	rol field is received.						
Test	Simulator	· → UUT	IT						
conditions	<ul> <li>Simula</li> </ul>	itor mus	ust operate as mobile station.						
Test	1. Simula	ator sen	nds frames with test values assigned to type in IR						
procedure	contro	l field, i	in the order (1), (2).						
	2. UUT receives frames, and test program for mobile station is used to								
	check	messag	ges.						
	Test value	e patteri	rn						
		Item	Test value						
	Туре		(1) 0011b (non-standard value)						
		(2) 0000b (standard value)							
Verification	Verify that frames with standard values are received normally and								
item	messa	ges can	n be extracted.						

No.	2-7-EX Item IR reception: Invalid synchronization information								
Test	Verify that no malfunction occurs when a frame with non-standard								
outline	synchro	nization	information in	IR control field is received.					
Test	Simulator	· → UU1	Γ						
conditions	• Simula	itor mus	st operate as m	nobile station.					
Test	1. Simula	ator sen	ds frames with	test values assigned to synchroniza	tion				
procedure	inform	nation in	IR control field	d, in the order (1), (2).					
	2. UUT receives frames, and test program for mobile station is used to								
	check	check messages.							
	Test value	e patter	n						
		Ite	m	Test value					
	Synchro	onization	n information	(1) 011b (non-standard value)					
		(2) 000b (standard value)							
Verification	Verify that frames with standard values are received normally and								
item	messa	ges can	be extracted.						

No.	2-8-EX	-8-EX Item IR reception: Invalid reserved						
Test	Verify that no malfunction occurs when a frame with non-standard							
outline	reserved	d field in	IR contro	ol field is received.				
Test	Simulator	· → UUT	_					
conditions	<ul> <li>Simula</li> </ul>	itor mus	t operate	as mobile station.				
Test	1. Simula	ator sen	ds frames	with test values assigned to reser	ved field			
procedure	in IR c	control f	ield, in the	e order (1), (2).				
	2. UUT re	2. UUT receives frames, and test program for mobile station is used to						
	check	messag	es.					
	Test value	e patteri	n					
		Item		Test value				
	Reserve	ed		(1) 1b (non-standard value)				
	(2) 0b (standard value)							
Verification	<ul> <li>Verify that frames with standard values are received normally and</li> </ul>							
item	messa	ges can	be extrac	ted.				

No.	2-9-EX	Item	IR reception: Invalid timestamp							
Test	Verify that no malfunction occurs when a frame with non-standard									
outline	timestamp in IR control field is received.									
Test	Simulator → UUT									
conditions	• Simula	itor mus	ust operate as mobile station.							
Test	1. Simula	ator sen	ends frames with test values assigned to timestamp in							
procedure	IR control field, in the order (1), (2).									
	2. UUT re	eceives	s frames, and test program for mobile station is used to							
	check	messag	ges.							
	Test value	e patteri	rn							
		Item	Test value							
	Timesta	ımp	(1) 1000000 (out-of-range value)							
	(2) 0 (in-range value)									
Verification	Verify that frames with in-range values are received normally and									
item	messages can be extracted.									

No.	2-10-EX	Item	IR	reception	: In	valid	roadside-to-vehicle				
NO.	2-10-LX	Item		•			Toduside-to-verticle				
				nunication							
Test	Verify that no malfunction occurs when a frame with non-standard										
outline	roadside-to-vehicle communication period information (roadside-to-vehicle										
	communication period length) in IR control field is received.										
Test	Simulator	· → UUT	•								
conditions	<ul> <li>Simula</li> </ul>	itor mus	t oper	ate as mob	ile statio	n.					
Test	1. Simula	ator send	ls fram	nes with tes	values a	assigne	d to roadside-to-vehicle				
procedure	comm	unication	perio	d informati	on (roads	side-to-	-vehicle communication				
	period	length) i	in IR c	ontrol field,	in the or	der (1)	, (2).				
	2. UUT r	eceives f	frames	s, and test	orogram	for me	obile station is used to				
	check	messag	es.								
	Test value	e patterr	า								
		Item				Test va	alue				
	Transfe	r count		Period 1: 0	1b, Peri	od 2: (	02b, Others: 00b				
	Roadsic	le-to-vel	nicle	(1) All per	ods: 0 u	nits (o	ut-of-range value)				
	commu	communication (2) Period 1: 63 units, Period 2: 1 unit,									
	period I	ength_		Others: 0 units (in-range value)							
Verification	Verify that frames with in-range values are received normally and										
item	messa	messages can be extracted.									

No.	2-11-EX Item	IR reception: Invalid enhanced field								
Test	Verify that no malfunction occurs when a frame with non-standard									
outline	enhanced field in IR control field is received.									
Test	Simulator → UUT									
conditions	<ul> <li>Simulator must</li> </ul>	operate as mobile station.								
Test	1. Simulator send	s frames with test values assigned to enhanced field								
procedure	in IR control fie	eld, in the order (1), (2).								
	2. UUT receives fr	rames, and test program for mobile station is used to								
	check message	S.								
	Test value pattern									
	Item	Test value								
	Enhanced field	Enhanced field (1) FFh (non-standard value)								
	(2) 00h (standard value)									
Verification	Verify that frames with standard values are received normally and									
item	messages can be extracted.									

No.	3-9-EX	Item	L7 reception: Invalid ApplicationDataLength							
Test outline	Verify that a received ASDU with non-standard ApplicationDataLength is properly discarded.									
Test conditions	Simulator	Simulator → UUT								
Test procedure	Simulator sends frames with test values set as ASDU length, order (1), (2), (3).      UUT receives frames, and test program for mobile station is uncheck messages.      Test value pattern      Item									
	(2) 0 octets (in-range value) (3) 1500 octets (in-range value)									
Verification item	<ul> <li>Verify that frames with out-of-range values are not received, and frames with standard values are received normally and messages can be extracted.</li> </ul>									

### Chapter 5 Simulator Specifications

Testing Systems include measuring instrument and a simulator. The basic functionality of the simulator is to provide the capability for two-way communication with mobile stations.

The simulator also is to incorporate a test program that makes use of the test program for mobile stations to perform connectivity tests.

The connection format between the simulator and the UUT (Unit Under Test) is to be based on the content of the ARIB Technical Report TR-T20 (700 MHz Band Intelligent Transport Systems Test Items and Conditions for Mobile Station Compatibility Confirmation).

#### 5.1 General items

The specifications in this chapter are intended as reference to be used when designing and manufacturing a simulator for testing the connectivity of land mobile radio stations for use in 700 MHz band intelligent transport systems.

#### 5.1.1 Standard to follow

Regarding points not explicitly covered in this chapter, the following standard is to be followed:

Association of Radio Industries and Businesses (hereinafter referred to as "ARIB") STD-T109 "700 MHz Band Intelligent Transport Systems"

#### 5.1.2 Reference standards

- (1) Radio Law (Ordinance Regulating Radio Equipment, etc.)
- (2) Telecommunications Business Law (Ordinance Regulating Business Equipment, etc.)
- (3) Japan Industrial Standards (JIS)
- (4) ITS Info-communications Forum Guidelines
- (5) The Telecommunication Technology Committee Standards
- (6) Guide Book of Electrical Equipment
- (7) Technical reference material from Nippon Telegraph and Telephone Corporation (NTT)
- (8) Japan Approvals Institute for Telecommunications Equipment (JATE) Standards

### 5.1.3 Compliance certifications to obtain (recommended)

The simulator constructed according to the specifications in this chapter should obtain all required technical compliance certifications as specified by the Radio Law. The required technical compliance certifications will depend on the testing environment.

#### 5.1.4 Items not explicitly stated

Items not explicitly stated in this chapter may be dealt with at the discretion and the responsibility of the operator constructing the simulator.

### 5.2 System configuration

#### 5.2.1 Test system configuration and simulator positioning




Fig.5-1 Test System Configuration and Simulator

The simulator specified in this chapter is to be connected by wired and wireless connection and incorporated into the overall system. It is denoted by the bold frame in Fig. 5-1. The simulator serves as the testing system within the test bed as described in section 4.2.3.

#### 5.2.2 Interface points

The simulator has two interface points. The wireless interface point is called the test

demarcation point. The wired interface point is called the external connection demarcation point.

### 5.2.3 Interface types

The test demarcation point, which represents the wireless interface, is to be connected either by coaxial cable or by antenna. For details, see the Technical Report.

The external connection demarcation point, which represents the wired interface, is to use a standard Ethernet connection compliant with 10BASE-T or higher.

### 5.3 Equipment configuration and structure

### 5.3.1 Equipment configuration

As shown in Fig. 5-2, the simulator configuration includes the interface section, communication control section, RF section, information processing section, and sensor signal section. The antenna part in the RF section must be a standard antenna with specifications as determined by the operation management organization.




Fig.5-2 Equipment Configuration

#### 5.3.2 General items

The simulator described in this chapter should be solid and sturdy, both in mechanical and electrical terms.

#### 5.3.3 Description of equipment

The simulator described in this chapter shall provide the functional equivalent of multiple mobile stations and multiple base stations in a 700 MHz band intelligent transport system and shall be capable of testing the connectivity of UUT. It also shall implement a test program for efficiently carrying out such tests.

CSMA/CA access control is not mandatory.

### 5.3.4 Operation environment (recommended)

Ambient ratings

Temperature range for guaranteed performance: 0°C to +45°C

Relative humidity: 10% to 90%

Electromagnetic environment: Normal urban environment noise level

Spurious radiation: Compliant with Radio regulation and ARIB standards as well

as VCCI Class A

Grounding: Type III grounding desirable

### 5.3.5 Power supply specifications (recommended)

The main equipment should satisfy the following requirements.

Power supply voltage: 100 to 240 V AC,  $\pm 10\%$ , 50 – 60 Hz

Power supply voltage fluctuations: Performance guaranteed over a range of  $\pm 10\%$ 

from rated voltage.

Momentary power interruption handling: At a temperature of 24°C ±4°C, operation

should be maintained for up to 40 ms with a 100% drop

Power consumption: Max. 100 VA with maximum load

Protection equipment: Surge protection should be implemented.

Insulation resistance/strength: Insulation resistance 10 megohms or better at DC

500V Megger

Insulation strength 2000 V AC for 1 minute

Insulation resistance value applies to condition with protection devices in place. Insulation strength value

applies to condition without protection devices.

Power switch: Construction should incorporate an externally operated

power switch.

Power indicator lamp: An indicator lamp showing when the system is powered

should be installed at an easy to see location.

### 5.3.6 RF input

The simulator shall be configured to allow a cable connection to the UUT for test purposes, so that it can receive 10 mW/MHz which is the transmission output power of the UUT.

### 5.3.7 Reference signal

The simulator may have to operate in conjunction with other systems (including other simulators if multiple simulators are used) and the vector signal generator. Synchronization in such a case should be based on a reference signal such as defined below. However, with regard to the vector signal generator, the operation management organization shall determine the concrete values.

Frequency: 10 MHz

• Output level: ≥10 dBm

Output impedance: 50 ohms

• Input level: 0 to 20 dBm

Input impedance: 50 ohms

### 5.3.8 Trigger signal

The simulator shall incorporate a profile function (see Fig. 5-3) that enables a trigger signal whose High and Low timing can be set in 1  $\mu$ s units for frames transmitted within a period of 104 ms or higher (settable in 1 ms units).

The output specifications of the trigger signal should be as follows.

• Output level: TTL and CMOS compatible level signals can be output.




Fig.5-3 Frame Transmission Concept for Profile Function (Example) (TR2-2-5)

NOTE

#### 5.4 Major functions

Operation mode

No.

6

The major functions of the simulator are shown in Table 5-1 as operation modes. Besides the operation modes where the simulator functions as one mobile station or one base station, there are also modes that simulate simultaneous operation of base station and mobile station (switched as required within a 100 ms transmission period) and operation as multiple mobile stations or multiple base stations.

1 Mobile station (single) mode Operate as 1 mobile station. 2 Base station (single) mode Operate as 1 base station. 3 Operate as 1 base station and 1 mobile Base station (single)/ mobile station (single) mode station and enable separate frame transmission for each. IR control field (synchronization information, timestamp) for each frame must be settable to arbitrary values. 4 Mobile station (multiple) Operate as multiple mobile stations and mode enable separate frame transmission for each. IR control field (synchronization information, timestamp) for each frame must be settable to arbitrary values. 5 Base station (single)/ mobile Operate as 1 base station and multiple station (multiple) mode mobile stations and enable separate frame transmission for each. IR control field (roadside-to-vehicle communication period information) for each frame must be settable to arbitrary values.

Table 5-1 Operation Modes

Operation outline

Operate as multiple base stations and

enable separate frame transmission for

IR control field (roadside-to-vehicle communication period) for each frame must be settable to arbitrary values.

#### 5.4.1 Mobile station functions

Base station (multiple) mode

The mobile station functions to be implemented by the simulator are listed in Table 5-2. Other functions are to follow the Standard.

each.

Table 5-2 Mobile Station Functions

			NOTE				
No.	Function	PMD/PLCP	MAC	LLC	IVC-RVC	L7	
1	Set transmission data rate	0	-	_	_	0	See Standard
2	Set transmission data length	-	-	-	-	0	See section 5.4.1.1
3	Set variable attenuation	0	-	-	-	_	See section 5.4.1.2
4	Set transmission frame interval	-	-	-	-	0	See section 5.4.1.3
5	Set transmission frame count	-	-	-	-	0	See section 5.4.1.4
6	Set MAC control field (radio station identification code)	-	0	-	-	_	See section 5.4.1.5
7	Set LLC control field (address field)	-	-	0	-	_	See section 5.4.1.6
8	Set LLC control field (control field)	-	-	0	-	-	See section 5.4.1.7
9	Set LLC control field (protocol identifier)	-	-	0	-	-	See section 5.4.1.8
10	Set IR control field (protocol version number)	-	-	-	0	_	See section 5.4.1.9
11	Set IR control field (type)	-	-	-	0	_	See section 5.4.1.10
12	Set IR control field (synchronization information)	-	-	-	0	-	See section 5.4.1.11
13	Set IR control field (reserved)	_	-	_	0	-	See section 5.4.1.12
14	Set IR control field (timestamp)	_	0	_	0	_	See section 5.4.1.13
15	Set IR control field (roadside-to-vehicle communication period	-	-	-	0	-	See section 5.4.1.14

	information)						
16	Set IR control field (enhanced field)	-	-	_	0	-	See section 5.4.1.15
17	Set L7 header (security classification information)	-	-	-	-	0	See section 5.4.1.16
18	Set L7 header (application associated information)	I	_	_	I	0	See section 5.4.1.17
19	Set invalid frame transmission (security)	Т	-	_	-	0	See section 5.4.1.18
20	Indicate reception data rate	0	ı	I	I	0	See section 5.4.1.19
21	Indicate reception data (ASDU) length	-	-	-	-	0	See Standard
22	Indicate reception data (ASDU) content	-	-	-	-	0	See Standard
23	Indicate reception frame count	-	ı	-	-	0	See section 5.4.1.20
24	Indicate frame reception timestamp	T	0	I	I	ı	See section 5.4.1.21
25	Indicate MAC control field (destination address) information (reception)	I	0	I	I	0	See section 5.4.1.22
26	Indicate LLC control field (address field) information (reception)	-	-	0	-	-	See section 5.4.1.23
27	Indicate LLC control field (control field) information (reception)	-	-	0	-	-	See section 5.4.1.24
28	Indicate LLC control field (Protocol identifier) information (reception)	-	-	0	-	-	See section 5.4.1.25
29	Indicate IR control field (synchronization information) (reception)	-	-	-	0	-	See section 5.4.1.26

30	Indicate IR control field (timestamp) information (reception)	-	_	-	0	-	See section 5.4.1.27
31	Indicate IR control field (roadside-to-vehicle communication period information) (reception)	-	-	-	0	-	See section 5.4.1.28
32	Indicate IR control field (protocol version number) information (reception)	-	-	ı	0	ı	See section 5.4.1.29
33	Indicate IR control field (type) information (reception)	-	-	1	0	-	See section 5.4.1.30
34	Indicate IR control field (reserved) information (reception)	-	-	I	0	ı	See section 5.4.1.31
35	Indicate IR control field (enhanced field) information (reception)	-	-	-	0	-	See section 5.4.1.32
36	Indicate L7 header (version) information (reception)	-	-	-	-	0	See section 5.4.1.33
37	Indicate L7 header (security classification information) (reception)	-	-	ı	l	0	See section 5.4.1.34
38	Indicate L7 header (reserved) information (reception)	_	-	-	-	0	See section 5.4.1.35
39	Indicate L7 header (application associated information) (reception)	-	-	-	-	0	See section 5.4.1.36

### 5.4.1.1 Set transmission data length

The function must allow setting the transmission data length (ASDU) to 0/32/100/1501 octets.

The function must allow setting the LPDU length to 0/96 octets.

### 5.4.1.2 Set variable attenuation

The function must allow varying the output power of the simulator to achieve an output of -50 dBm and -17 dBm or higher.

Taking also the antenna characteristics into account, it must be possible to set values so that tests 2-2-4 and 2-2-5 in the Technical Report can be performed.

The reason why a simulator output of -17 dBm or higher is required is explained in Annex B "Simulator Output Levels for Tests TR 2-2-4/TR 2-2-5."

#### 5.4.1.3 Set transmission frame interval

The function must allow setting the transmission frame interval at the antenna terminal of the simulator to 2 ms and 50  $\mu$ s.

#### 5.4.1.4 Set transmission frame count

The function must enable frame transmission by the following two methods.

· Set transmission frame count to 1, 2, 3

When simulating multiple mobile stations, the transmission frame count for each mobile station must be settable to 1.

· Transmit frames until transmission is stopped (continuous transmission)

In this case, transmission frames must be counted and it must be possible to display the count.

A profile function that enables free setting of transmission frames (transmission data length) and transmission frame interval (in 1  $\mu$ s units) for a period of 100 ms and 104 ms or higher (settable in 1 ms units) and 200 ms must be provided.

Furthermore, the number of repetitions for the period set with the profile function must be settable to 500 and 1000.

#### 5.4.1.5 Set MAC control field (radio station identification code)

The function must allow setting the radio station identification code in the MAC control field to an arbitrary value for each transmitted frame.

### 5.4.1.6 Set LLC control field (address field)

The function must allow setting the address field in the LLC control field to an arbitrary value for each transmitted frame.

#### 5.4.1.7 Set LLC control field (control field)

The function must allow setting the control field in the LLC control field to an arbitrary value for each transmitted frame.

### 5.4.1.8 Set LLC control field (protocol identifier)

The function must allow setting the protocol identifier field in the LLC control field to an arbitrary value for each transmitted frame.

### 5.4.1.9 Set IR control field (protocol version number)

The function must allow setting the protocol version number in the IR control field to an arbitrary value for each transmitted frame.

#### 5.4.1.10 Set IR control field (type)

The function must allow setting the type in the IR control field to an arbitrary value for each transmitted frame.

### 5.4.1.11 Set IR control field (synchronization information)

The function must allow setting the synchronization information in the IR control field to an arbitrary value for each transmitted frame, as shown below.

$$(b2, b1, b0) = (1, 0, 0), (1, 0, 1), (1, 1, 0), (1, 1, 1), (0, 0, 0), (0, 1, 1)$$

### 5.4.1.12 Set IR control field (reserved)

The function must allow setting the reserved field in the IR control field to an arbitrary value for each transmitted frame.

### 5.4.1.13 Set IR control field (timestamp)

The function must allow setting the timestamp field in the IR control field to an arbitrary value in the range from 0 to 1000000 for each transmitted frame. It must also be possible to independently set the timer of the base station and mobile station to separate values.

### 5.4.1.14 Set IR control field (roadside-to-vehicle communication period information)

The function must allow setting arbitrary values for roadside-to-vehicle communication period information (b7, b6: transfer count, b5 to b0: roadside-to-vehicle communication period duration) for the roadside-to-vehicle communication period 1 to 16 (length of all fields 16 octets) for each transmitted frame.

#### 5.4.1.15 Set IR control field (enhanced field)

The function must allow setting the enhanced field in the IR control field to an arbitrary value for each transmitted frame.

### 5.4.1.16 Set L7 header (security classification information)

The function must allow setting the security classification information in the L7 header to an arbitrary value for each transmitted frame.

#### 5.4.1.17 Set L7 header (application associated information)

The function must allow setting the application associated information in the L7 header to an arbitrary value for each transmitted frame.

### 5.4.1.18 Set invalid frame transmission (security)

The function must allow sending a signal corresponding to an invalid message frame (frame with out-of-range data structure or frame created with out-of-range security parameter setting) for security processing by the UUT.

#### 5.4.1.19 Indicate reception data rate

The function must indicate the data rate of a normally received frame.

#### 5.4.1.20 Indicate reception frame count

The function must allow indicating the count of normally received frames.

### 5.4.1.21 Indicate frame reception timestamp

The function must allow indicating the time (rxtime) when a frame was received.

When the simulator functions as a base station and mobile station, or multiple mobile stations, a non-synchronized condition will exist between the base station and mobile station, or multiple mobile stations, and it is necessary to know the time at the base station and each mobile station at the point of frame reception. The simulated base station and mobile stations therefore must have a timer.

5.4.1.22 Indicate MAC control field (destination address) information (reception)

The function must allow indicating the destination address in the MAC control field of the normally received MPDU.

5.4.1.23 Indicate LLC control field (address field) information (reception)

The function must allow indicating the address field in the LLC control field of the normally received LPDU.

5.4.1.24 Indicate LLC control field (control field) information (reception)

The function must allow indicating the control field in the LLC control field of the normally received LPDU.

5.4.1.25 Indicate LLC control field (protocol identifier) information (reception)

The function must allow indicating the protocol identifier field in the LLC control field of the normally received LPDU.

5.4.1.26 Indicate IR control field (synchronization information) (reception)

The function must allow indicating the synchronization information in the IR control field of the normally received IPDU.

5.4.1.27 Indicate IR control field (timestamp) information (reception)

The function must allow indicating the timestamp in the IR control field of the normally received IPDU.

5.4.1.28 Indicate IR control field (roadside-to-vehicle communication period information) (reception)

The function must allow indicating the roadside-to-vehicle communication period information (transfer count, roadside-to-vehicle communication period duration) in the IR control field of the normally received IPDU.

5.4.1.29 Indicate IR control field (protocol version number) information (reception)

The function must allow indicating the protocol version number in the IR control field of the normally received IPDU.

#### 5.4.1.30 Indicate IR control field (type) (reception)

The function must allow indicating the identification information in the IR control field of the normally received IPDU.

### 5.4.1.31 Indicate IR control field (reserved) information (reception)

The function must allow indicating the reserved field in the IR control field of the normally received IPDU.

#### 5.4.1.32 Indicate IR control field (enhanced field) information (reception)

The function must allow indicating the enhanced field in the IR control field of the normally received IPDU.

### 5.4.1.33 Indicate L7 header (version) information (reception)

The function must allow indicating the version information in the L7 header of the normally received APDU.

#### 5.4.1.34 Indicate L7 header (security classification information) (reception)

The function must allow indicating the security classification information in the L7 header of the normally received APDU.

### 5.4.1.35 Indicate L7 header (reserved) information (reception)

The function must allow indicating the reserved information in the L7 header of the normally received APDU.

#### 5.4.1.36 Indicate L7 header (application associated information) (reception)

The function must allow indicating the application associated information in the L7 header of the normally received APDU.

#### 5.4.1.37 Others

The first octet of the ASDU in a frame sent by the simulator must be as follows.

Response request frame: "E0h"

Other than above: "00h"

For the TR 2-2-4 and TR 2-2-5 tests, the frame transmission described below must be repeated 1000 times.

- 1. Simulator sends response request frame.
- 2. Starting from 50  $\mu$ s after sending the response request frame, simulator sends interference frames by repeating transmission/stop pattern with a 50  $\mu$ s frame interval until the total transmission time exceeds 101 ms.
- 3. At least 1 ms after receiving a response frame from the UUT, the simulator returns to step 1 and repeats the procedure.

For steps 1 to 3 above, a profile function that enables free setting of transmission frames (transmission data length) and transmission frame interval (in 1  $\mu$ s units) for a

period of 104 ms or higher (settable in 1 ms units) must be provided. The concept of frame transmission with the profile function is shown in Fig. 5-3.

The number of response frames received from the UUT must be counted and it must be possible to display the count.

# 5.4.2 Base station functions

The base station functions to be implemented by the simulator are listed in Table 5-3. Other functions are to follow the Standard.

Table 5-3 Base Station Functions

	. 42.10	Applicable leven					
	Function	Applicable layer					]
No.		PMD/ PLCP	MAC	LLC	IVC-RVC	L7	NOTE
1	Set transmission data rate	0	-	-	-	0	See section 5.4.2.1
2	Set transmission data (ASDU) length	-	-	-	-	0	See section 5.4.2.2
3	Set transmission frame count	_	_	_	-	0	See section 5.4.2.3
4	Set transmission frame interval	-	_	_	_	0	See section 5.4.2.4
5	Set variable attenuation	0	_	_	_	I	See section 5.4.2.5
6	Set IR control field (synchronization information)	_	_	_	0	I	See section 5.4.2.6
7	Set IR control field (timestamp)	_	_	_	0	ı	See section 5.4.2.7
8	Set IR control field (roadside-to-vehicle communication period information)	-	_	_	0	_	See section 5.4.2.8
9	Set invalid frame transmission (security)	_	_	_	-	0	See section 5.4.2.9
10	Indicate frame reception timestamp	_	0	_	_	-	See section 5.4.2.10

11	Indicate IR control field (synchronization information) (reception)	_	_	_	0	-	See section 5.4.2.11
12	Indicate IR control field (timestamp) information (reception)	-	_	_	0	-	See section 5.4.2.12
13	Indicate IR control field (roadside-to-vehicle communication period information) (reception)	-	-	-	0	_	See section 5.4.2.13

#### 5.4.2.1 Set transmission data rate

This function must be compliant with the Standard. Available transmission data rates are listed in Table 5-4.

Data rate	Subcarrier modulation	Encoding ratio			
3 Mbps	BPSK	1/2			
4.5 Mbps	BPSK	3/4			
6 Mbps	QPSK	1/2			
9 Mbps	QPSK	3/4			
12 Mbps	16QAM	1/2			
18 Mbps	16QAM	3/4			

Table 5-4 Base Station Transmission Data Rates

# 5.4.2.2 Set transmission data (ASDU) length

The function must allow setting the length to an arbitrary value (0 to 1500 octets) suitable for transmission data rates (see section 5.4.2.1).

### 5.4.2.3 Set transmission frame count

The function must allow setting the frame count to an arbitrary value (1 to x) suitable for the transmission data rate and data length.

When simulating multiple base stations, the transmission frame count for each base station must be settable to 1.

The value of x is determined by the operation management organization.

A profile function that enables free setting of transmission frames (transmission data length) and transmission frame interval (in 1  $\mu$ s units) for a control period of 100 ms and 200 ms must be provided. Furthermore, the number of repetitions for the period set with the profile function must be settable to 500 and 1000.

#### 5.4.2.4 Set transmission frame interval

The function must allow setting the transmission frame interval at the antenna terminal of the simulator to the shortest space.

#### 5.4.2.5 Set variable attenuation

The function must allow setting the transmission power of the simulator to -50 dBm.

Taking also the antenna characteristics into account, it must be possible to set values so that the tests can be performed.

# 5.4.2.6 Set IR control field (synchronization information)

The function must allow setting the synchronization information in the IR control field to an arbitrary value for each transmitted frame, as shown below.

$$(b2, b1, b0) = (1, 0, 0), (0, 0, 0)$$

# 5.4.2.7 Set IR control field (timestamp)

The function must allow setting the timestamp field in the IR control field to an arbitrary value in the range from 0 to 999999 for each transmitted frame. It must also be possible to independently set the timer of the base station and mobile station to separate values.

# 5.4.2.8 Set IR control field (roadside-to-vehicle communication period information)

The function must allow setting arbitrary values for roadside-to-vehicle communication period information (b7, b6: transfer count, b5 to b0: roadside-to-vehicle communication period duration) for the roadside-to-vehicle communication period 1 to 16 (length of all fields 16 octets) for each transmitted frame.

### 5.4.2.9 Set invalid frame transmission (security)

The function must allow sending a signal corresponding to an invalid message frame (frame with out-of-range data structure or frame created with out-of-range security parameter setting) for security processing by the UUT.

#### 5.4.2.10 Indicate frame reception timestamp

The function must allow indicating the time (rxtime) when a frame was received.

When the simulator functions as a base station and mobile station, or multiple mobile stations, a non-synchronized condition will exist between the base station and mobile station, or multiple mobile stations, and it is necessary to know the time at the base station and each mobile station at the point of frame reception. The simulated base station and mobile stations therefore must have a timer.

#### 5.4.2.11 Indicate IR control field (synchronization information) (reception)

The function must allow indicating the synchronization information in the IR control field of the normally received IPDU.

# 5.4.2.12 Indicate IR control field (timestamp) information (reception)

The function must allow indicating the timestamp in the IR control field of the normally received IPDU.

5.4.2.13 Indicate IR control field (roadside-to-vehicle communication period information) (reception)

The function must allow indicating the roadside-to-vehicle communication period information (transfer count, roadside-to-vehicle communication period duration) in the IR control field of the normally received IPDU.

# 5.4.3 Test programs

# 5.4.3.1 Definition of test program for simulator

The simulator must implement a test program that facilitates the conducting of connectivity testing with the UUT. However, procedural programs intended to completely automate the test process are outside the scope of the current specifications.

# 5.4.3.2 Implementation of test program for simulator

Fig. 5-4 shows the test program structure for the simulator.




Fig. 5-4 Test Program Structure for Simulator

The test program for simulator covers the six operation modes to be realized by the simulator, as listed in Table 5-1, and starts the mobile station functions and base station functions as required. The implementation method and startup method are not specified. The test program for simulator must incorporate the setting and reading of the parameter of the simulator used for testing the UUT, and also must incorporates the logging function of the measured data. Furthermore, functions for testing error handling and for maintenance management are also required.

#### 5.4.4 Error handling function

The simulator shall incorporate a function for transmitting a signal that is suitable for checking the error handling performance of the UUT. An error in the context of this document envisions a condition as defined in the SDL diagram, but until the SDL diagram has been finalized, the capability for checking the exception handling performance of the UUT is desirable.

"Exception handling" in this document is as defined in the section on Exception test in Chapter 4.

The specifications required of the simulator with regard to exception handling must be such as to allow performing the tests of Chapter 4. In concrete terms, this means the ability to transmit the basic parameters for a specific Interoperability Verification Test.

# 5.5 Maintenance management function

### 5.5.1 Self-diagnosis function

The simulator specified in this chapter shall have a self-diagnosis function that can detect defects and error conditions and can provide notification of such conditions to external equipment. Some examples of defects and error conditions are listed below.

- · Internal temperature problem
- · Fan stop
- Frequency synthesizer out-of-lock condition
- · RAM/ROM checksum error
- · Transmission data rate / data length / frame count / data content error

With regard to defects and error conditions that cannot be detected by the self-diagnosis function, a provision must be made to evaluate these by using test bed facilities such as the standard mobile station, etc.

#### 5.5.2 Monitor terminal

The simulator specified in this chapter shall be equipped with a connection for a terminal (monitor terminal) or similar equipment that allows monitoring the internal condition of the simulator. The monitor terminal must allow making parameter settings and issuing commands to the UUT. The monitor terminal shall possess an interface (GUI, etc.) that facilitates operation by the user.

# 5.5.3 Log data storage function

The simulator specified in this chapter shall be equipped with a storage device for storing log data obtained during testing. Storage can be implemented either in the simulator itself or in the monitor terminal.

# Chapter 6 Definitions and Abbreviations

# 6.1 Glossary

The following definitions are used in the glossary of this Guideline.

### [IR control field]

A field included in the IPDU, comprising the protocol version, type, synchronization information, reserved field, timestamp, roadside-to-vehicle communication period information, and enhanced field.

# [IVC-RVC Protocol Data Unit (IPDU)]

Data unit exchanged between the inter-vehicle and roadside-to-vehicle communication (IVC-RVC) control information layers.

# [Application Service Data Unit (ASDU)]

Data unit exchanged between application and layer 7.

# [Mobile station]

A radio station installed in a vehicle or similar. Same meaning as "land mobile station".

### [MAC Service Data Unit (MSDU)]

Data unit exchanged between LLC sublayer and MAC sublayer of layer 2.

#### [MAC sublayer]

Part where telecommunications management of the transmission channel of layer 1 is conducted.

# [LLC sublayer]

To conduct packet transmission between entities in a high-ranking layer, this layer provides a non-confirmation connectionless type service.

#### [LLC Protocol Data Unit (LPDU)]

Data unit exchanged between the LLC sublayers of layer 2.

# [Octet]

Element composed of a binary array of 8 bits.

#### [Step attenuator]

A device providing attenuation in adjustable steps of 10 dB and 1 dB.

### [Base station]

A radio station set up at the roadside.

#### [Antenna connector]

Also called antenna port, this is a coaxial connector for connecting the antenna of the UUT. It may be mounted directly on the chassia of the radio station or employ a pigtail configuration with a cable protruding from the chassia and having a connector at the end.

### [Cable connection]

A configuration where the antenna terminal (coaxial connector) of the radio station is connected directly to the connectivity testing equipment via a coaxial cable.

### [Shielded room / shielded box]

A larger (room) or smaller (box) device that uses metal plating or other means to prevent or attenuate electromagnetic radiation passing from the inside to the outside and vice versa.

### [Signal analyzer]

A measuring equipment, usually called a vector signal analyzer, that is used for measurement and allows various types of analysis and evaluation of modulated signals. By implementing signal analysis software for wireless LAN, it allows analysis and evaluation of OFDM signals. The equipment enables measurement of the three elements determining modulation accuracy, namely transmitter center frequency leakage, transmitter spectral flatness, and transmitter constellation error. The packet error rate (PER) can also be measured.

#### [Testing program]

A test program is a program either implemented in the UUT, standard mobile station, standard base station, and simulator, or implemented in external equipment, serving to perform input and output of test data, transmission and reception of test messages. According to requirements, the program also comprises functions that allow the display and evaluation of test results.

# [Simulator]

A equipment comprising the communication interface functions of both base station and mobile station, and capable of two-way communication with the UUT via RF signals. The specifications are described in Chapter 5 of this Guideline.

# [Connectivity testing equipment]

Test equipment to which the UUT can be connected, with the aim of measuring the functions and performance of the UUT. The connectivity testing equipment category includes measuring equipment and the simulator.

### [Data rate]

A quantity expressing the data transfer speed. Same meaning as "RATE" in the SIGNAL field.

### [Packet Error Rate (PER)]

A ratio calculated from the number of successfully received packets vs. the number of transmitted packets.

### [Packet error rate counter]

A measuring equipment for determining the packet error rate. Commonly consists of a bit error counter and a computer running dedicated software for calculating the packet error rate.

# [Unit Under Test (UUT)]

The land mobile radio station whose radio equipment is being tested.

### [Standard]

A document by the Association of Radio Industries and Businesses (ARIB) specifying standard requirements for consumer equipment utilizing radio waves.

### [Standard base station]

A reference base station produced by each respective manufacturer and certified by the operation management organization.

#### [Standard mobile station]

A reference mobile station produced by each respective manufacturer and certified by the operation management organization.

# [Protocol Data Unit (PDU)]

Data unit exchanged between same-level protocols.

#### [Preamble]

Refers to the PLCP preamble, which is first part of the transmitted/received signal serving to enable signal detection and synchronization.

#### [Primitive]

A basic instruction used for requesting and providing services between layers.

#### [Vector signal generator]

A signal generator allowing vector modulation, able to produce various kinds of modulated signals, non-modulated waves, etc. Through the use of functional options, a vector signal generator can also produce OFDM signals.

# [Wireless connection]

A configuration where the radio station with integrated antenna is connected to the connectivity testing equipment via a radio wave link.

# [Land mobile station]

A radio station installed in a vehicle or similar. Same meaning as "mobile station".

### [Layer 1]

A conceptual hierarchy indicating the physical medium in which signal transmission occurs. (Also called the physical layer, providing the interface for layer 2.)

### [Layer 2]

A conceptual hierarchy indicating the medium in which data link control occurs. (Also called the data link layer, providing the interface for the inter-vehicle and roadside-to-vehicle communication control information layer.)

# [Layer 7]

A conceptual hierarchy indicating the medium in which general processing functions for various applications are performed. (Provides the interface for applications.)

# [Roadside-to-vehicle communication period information]

Information included in the IR control field of the IPDU, consisting of the transfer count and roadside-to-vehicle communication period duration.

### 6.2 Abbreviations

[A]

AC: Alternate Current

ALME: Application Layer Management Entity

ARIB: Association of Radio Industries and Businesses

ASDU: Application Service Data Unit

[B]

BPSK: Binary Phase Shift Keying

[C]

CCA: Clear Channel Assessment

CSMA: Carrier Sense Multiple Access

[D]

DC: Direct Current

DSAP: Destination Service Access Point

[E]

[F]

FI: Frame Information

[G]

GPS: Global Positioning System
GUI: Graphical User Interface

[H]

[1]

IPDU: IVC-RVC Protocol Data Unit
ITS: Intelligent Transport Systems

IVC-RVC: Inter-Vehicle Communication - Roadside-to-Vehicle Communication

[J]

JATE: Japan Approvals Institute for Telecommunications Equipment

JIS: Japanese Industrial Standards

[K]

[L]

L1: Layer 1 (Physical Layer)
L2: Layer 2 (Data Link Layer)
L7: Layer 7 (Application Layer)

LLC: Logical Link Control
LPDU: LLC Protocol Data Unit

[M]

MAC: Medium Access Control

MSDU: MAC Service Data Unit

[N]

[O]

[P]

PDU: Protocol Data Unit

PLCP: Physical Layer Convergence Protocol

PMD: Physical Medium Dependent

[Q]

QAM: Quadrature Amplitude Modulation

QPSK: Quadrature Phase Shift Keying

[R]

RAM: Random Access Memory

RF: Radio Frequency

ROM: Read Only Memory

[S]

SDL: Specification and Description Language

SSAP: Source Service Access Point

[T]

TTC: Telecommunication Technology Committee

[U]

[V]

VCCI: Voluntary Control Council for Information Technology Equipment

[W]

[X]

[Y]

[Z]

[Blank]

# Annex A: Values Determined by Operation Management Organization

When performing the Interoperability Verification Test, specific numerical values must be used. However, actual values that cannot be specified as part of this Guideline are denoted here by the letter "x". Such values are to be set and specified by the operation management organization, i.e. the public or business entity that is responsible for services and/or operation of the 700 MHz band system, or an entity to which this task has been officially assigned.

This Guideline is based on the assumption that it will be used by the operation management organization, and therefore makes explicit use of "x" wherever necessary.

Table Annex-A lists all locations where "x" is used.

Table Annex-A List of Locations Where "x" Is Used

No.	Section number	Item	Notation	NOTE
1	2.5.2 Test description of physical layer	Test number TR 2-1-3	x dBm	Power value
2	3.4 Security test description	Test number 1, 2, 3, 4, 5, 6	Value x	Security parameter
3	4.3.2 Interoperability verification test parameters	Layer 7	Value x	ApplicationData
4	4.3.3.1 Test description for Interoperability test	Test number 4-1-IN	Value x	Security parameter
5	As above	As above	Value x	Encryption key
6	As above	Test number 4-4-IN	Value x	Security parameter
7	As above	As above	Value x	Encryption key
8	4.3.3.3 Test description for Performance test	Test number 4-2-PER	x µs	Setting value
9	As above	As above	Value x	Verification item
10	As above	Test number 4-3-PER	x µs	Setting value
11	As above	As above	Value x	Verification item
12	As above	Test number 4-4-PER	x µs	Setting value
13	As above	As above	Value x	Verification item
14	As above	Test number 4-5-PER	x µs	Setting value
15	As above	As above	x times	Test procedure
16	As above	As above	Value x	Verification item

# Annex B: Simulator Output Levels for Tests TR 2-2-4/TR 2-2-5

The spectrum analyzer conditions required for calculating the simulator output level for the TR 2-2-4 and TR 2-2-5 tests are given in B.1.

B.1 Reason why a UUT signal of -30 dBm or more is required at the spectrum analyzer input for TR 2-2-4/TR 2-2-5

The reason why the test conditions for TR 2-2-4 and TR 2-2-5 in the Technical Report are given as "UUT signal of -30 dBm or more required at spectrum analyzer input" is as follows.

The display noise level of a spectrum analyzer is commonly on the order of -150 dBm/Hz to -140 dBm/Hz.

In the TR 2-2-4/TR 2-2-5 test, the spectrum analyzer setting RBW = 10 MHz is used. Taking the bandwidth of 10 MHz ( $10\log(10 \text{ MHz}) = 70 \text{ dB}$ ) into account, the display noise level is -80 dBm to -70 dBm. In order to ensure that the level of the invalid signal packet occurring once every 1000 times (-30 dB with an Ave setting of 1000) is higher than the internal noise level of the spectrum analyzer (-70 dBm), i.e. to ensure that it is at least -60 dBm, the signal P2 at the spectrum analyzer input must be at least -30 dBm.

From the above, it follows that the display noise level of the spectrum analyzer must be -140 dBm/Hz or lower.

### B.2 Calculating the simulator output level

Assuming that spectrum analysis for TR tests is done with measuring equipment that supports physical layer tests and also implements spectrum analyzer functions, the display noise level of the measuring equipment should be on the order of about -150 dBm/Hz.

In section B.1, the display noise level of the spectrum analyzer is assumed to be at least -140 dBm/Hz. The -150 dBm/Hz requirement therefore can be met by inserting a 10 dB attenuator at the input of the spectrum analyzer. The internal mixer input level of the spectrum analyzer is about -10 dBm maximum. When the PAPR (Peak to Average Power Ratio) of the OFDM signal is 13 dB, the level that can be input to the spectrum analyzer is  $(-10 \text{ dBm} + 10 \text{ dB} \text{ (SA\_ATT}^{*1}) -13 \text{ dB (PAPR)} =) -13 \text{ dBm or lower.}$ 

To keep the P2 signal from the UUT at the spectrum analyzer input to -13 dBm or lower, the suitable values in the test configuration diagram for TR-2-2-4/TR 2-2-5 are as follows. UUT output level: +20 dBm, power divider insertion loss: 6 dB, cable loss:

disregarded, attenuation setting of step attenuator 2: 27 dB or higher.

The required condition for obtaining a level of -50 dBm for the signal from the simulator at the antenna terminal of the UUT is as follows. Simulator output: (-50 dBm + 27 dB (ATT2 $^{*2}$ ) + 6 dB + 0 dB (ATT1 $^{*3}$ ) =) -17 dBm or higher

- \*1: Attenuator at spectrum analyzer input
- \*2: Step attenuator 2 in test configuration diagram for TR 2-2-4/TR 2-2-5
- \*3: Step attenuator 1 in test configuration diagram for TR 2-2-4/TR 2-2-5

# Simulator output level ≥-17 dBm

The following diagram illustrates the conditions described above.




Fig.B-1 Test Configuration and Signal Level

•		
Parameter	Setting value	NOTE
UUT output level	20 dBm	
Power divider loss	6 dB	
Cable loss	0 dB	
Spectrum analyzer maximum input level (OFDM	-13 dBm	
signal input)		
Spectrum analyzer display noise level	-70 dBm/10 MHz	
Input level of simulator signal at UUT	-50 dBm	from Technical
		Documentation
Minimum spectrum analyzer input level of UUT	-30 dBm	from Technical
signal		Documentation

Table B-1 Test Requirements

$$P1 - ATT1 - 6 - ATT2 = -50$$
 (1)

$$P1 - ATT1 - 6 = P2 \le -13$$
 (2)

$$-30 \le (20 - ATT2 - 6) \le -13$$
 (3)

From equation (3), 
$$27 \le ATT2 \le 44$$
 (4)

From equation (2), P1 - ATT1 
$$\leq$$
 -7 (5)

From equation (1), 
$$P1 - ATT1 + 44 = ATT2$$
 (6)

From equation (6) and equation (4) 27  $\leq$  (P1 - ATT1 + 44)  $\leq$  44

$$-17 \le (P1 - ATT1) \le 0$$
 (7)

Relational expression to fulfill both equation (7) and equation (5)

$$-17 \le (P1 - ATT1) \le -7$$

When ATT1 = OdB

$$-17 \leq P1 \leq -7$$

When P1 is -7 dBm or higher, attenuated with ATT1 $^*$ , P1 must be made at least P1  $\geq$  -17 [dBm]

<sup>\*</sup> Setting range of ATT1 must be chosen so that UUT signal can be received by simulator.